

1/15/2017

ADDENDUM NO. 6
TO THE BID DOCUMENTS
(construction plans and bid package)
FOR THE
FRIENDSHIP FOREST WILDLIFE SANCTUARY
PARK RENOVATION PROJECT

Questions Received:

1. On sheet C-04 note says to remove at direction of owner. Please clarify what is to be removed.
2. On sheet C-04 overhead power to be removed, is the line active? Who owns the wire and poles?
3. Are the grades on the retaining wall indicating actual top of wall and bottom of wall?
4. Can a wall envelope be provided for the granite veneer wall?

Response to Questions:

1. **The 5' strip of existing asphalt and fence is to be removed. The "direction of owner" (typical note) denotes that the City's representative will be coordinating/working with the contractor for a particular construction task. The City's representative will provide guidance and coordinate with the selected contractor any extent of clearing outside of the 5' strip of asphalt being removed.**
2. **Overhead power appears to only be feeding existing street lights along the existing driveway. The city does not believe power is being provided to the service line inside the park. The city is not receiving billing from Georgia Power for this park. The city is the owner of the overhead power/lights. The selected contractor will need to coordinate with Georgia Power to ensure power is not being provide to these internal park service poles.**
3. **The top of wall is actual top of wall/cap stone. Bottom of wall elevation is finished grade at bottom of wall.**
4. **Retaining wall envelope is shown on C-24 – "Parking Lot Site Wall Detail".**