	LMIG 25/24, LKA & SPLOST IT Resurrating Project										
a	-	-	Avg. Width		Milling Depth		Asphalt Resurfacing; 12.5		4 IN Asphalt 19 mm	Aggregate	NOTES
Street Segment	From	То	(feet)	Length (feet)	(inches)	Milling (SY)	mm (TN); Spread Rate	mm (TN); Spread Rate (165		Surface Course	NOTES
							(220 LBS/SY)	LBS/SY)	LBS/SY)	(tons)	400 FT X 24 FT unsuitable
											subgrade - excavate with
											backhoe; backfill with 4
	E D L L		24	1.070	2	5 252	<b>57</b> 0	NA	224	200	inch 19 mm with
Jolly Street (north)	East Ponce de Leon	Mell Ave	24	1,970	2	5,253	578	NA	234	800	Aggregate Surface Course
											as directed by the project
L II. Court (co. d)	D. 1. 10()	C' L'	24	050	2	2,522	NT A	209	0	0	inspector
Jolly Street (south)	Rowland Street	City Limits	24 24	950	2 2	2,533	NA	209 NA	0	0	NA NA
Pecan Street	East Ponce de Leon	Jolly Ave	18	1,730 290	2	4,613 580	507 64	NA	0	0	NA
Lester Road	Clark Street	Smith Street							0	0	NA
Clark Street	Smith Street	Dead End	18 18	870 370	2	1,740	191 81	NA NA	0	0	NA
Lincoln Street	Smith Street	Clark Street	24	730	2	740	214	NA	0	0	NA
Smith Street	Lincoln Street	Montreal Road Dead End	16	250	2	444	49	NA	0	0	NA
Tribble Street Cleavemark Drive	Clark Street Norman Road	Dead End Dead End	26	1,450	2	444 4,189	49 461	NA	0	0	NA
Clydedale Drive	Cranford Drive	Cleavemark Drive	20	1,430	2	3,640	401	NA	0	0	NA
Cranford Drive	Rogers Street	Cleavemark Drive	20	890	2	2,571	283	NA	0	0	NA
Hill Street	North Indian Creek	West Hill Street	20	765	2	2,040	285	NA	0	0	NA
Thi Succi	Norun Indian Creek	west min Sueet	24	705	2	2,040	224	ha	0	0	
West Hill Street	Hill Street	Sams Road	24	758	2	2,021	222	NA	44	160	West Hill at culvert crossing - unsuitable subgrade - excavate with backhoe; backfill with Aggregate Surface Course as directed by the project inspector; 24 ft. x 75 ft.
Sams Road	Montreal Road	West Hill Street	23	750	2	1,917	211	NA	60	218	West Hill at Sams Road intersection -unsuitable subgrade - excavate with backhoe; backfill with 4 inch 19 mm with Aggregate Surface Course as directed by the project inspector; 24 ft. x 100 ft.
Maclaren Drive	Market Street	Dead End	23	1,650	2	4,217	464	NA	0	0	NA
Casa Drive	Mell Ave	Bridge	26	1,450	2	4,189	461	NA	0	0	NA
Casa Woods Drive (east)	Casa Drive	Cul-de-Sac	26	420	2	1,213	NA	100	0	0	NA
Casa Woods Drive (west)	Casa Drive	Cul-de-Sac	26	820	2	2,369	NA	195	0	0	NA
Lovejoy Street	Rowland Street	Church Street	24	215	2	573	63	NA	0	0	NA
Orchard Street	Jolly Ave	Pecan Street	24	580	2	1,547	NA	128	0	0	NA
SUBTOTAL				18,168		48,336	4,473	632	338	1,178	
					5% QTY INCREASE FOR UNFORESEEN PAVEMENT CONDITIONS		224	32			
TOTAL						48,336	4,697	664	338	1,178	

## LMIG 23/24, LRA & SPLOST II Resurfacing Project