

Form of Proposal

To: City of Clarkston
Clarkston, GA 30021

I/We the undersigned hereby offer and agree to supply and deliver the service(s) as outlined in the Request for Proposal documents. The signatures(s) below dignify the I/We have read and agree with the procedures outlined in the Request for Proposal documents.

I/We also agree no additional work shall be accepted outside of the scope of work outlined in this solicitation. If any additional work is requested, this must be assigned by the requesting department and approved by the City of College Purchasing Department, through a change order.

Proposal Submitted By:

Company Name	
Address	
City, State, Zip	
Phone	
Email	
Website	
Print/Type Name	
Signature	
Title	
Date	

COST of PROPOSAL

Bidding Company:

Company Rep:

Project Name:

ITEM NO.	DESCRIPTION	U/M	QTY	UNIT PRICE	LUMP SUM
150-1000	TRAFFIC CONTROL	LS	1		
210-0100	GRADING COMPLETE	LS	1		
310-1101	GR AGGR BASE CRS, INCL MATL	TN	14		
430-0160	PLAIN CONC; CL1 CONC, 6 IN THK ⁽⁷⁾	SY	33		
441-0018	DRIVEWAY CONCRETE, 8 IN ⁽⁶⁾	SY	75		
441-0104	CONC SIDEWALK, 4 IN.	SY	773		
441-0108	CONC SIDEWALK, 8 IN. THICK (ADA PEDESTRIAN RAMPS W/ YELLOW TRUCATED DOMES)	SY	299		
441-6012	CONC TYPE CURB & GUTTER, 6 IN X 24 IN	LF	5		
500-9999	CLASS B CONCRETE BASE (for granite reset)	CY	35		
511-1000	BAR REINF STEEL (#3 bars) (to be placed in the ramps)	LB	100		
611-5280	RESET GRANITE CURB ⁽¹⁾	LF	344		
754-4000	WASTE RECEPTACLE UNIT ⁽⁴⁾	EA	3		
754-5000	BENCH (5 FT) ⁽⁴⁾	EA	3		
NA	POROUS CONCRETE SIDEWALK ⁽²⁾	SY	12		
NA	TREE MAINTENANCE AND ROOT PRUNING ⁽³⁾	LS	1		
NA	LANDSCAPING (tree installations) ⁽⁵⁾	LS	1		
EROSION CONTROL					
161-1000	EROSION CONTROL	LS	1		
700-9300	SOD (Bermuda – Tifway 419)	SY	120		

SIGNING AND MARKING					
636-1033	HIGHWAY SIGNS, TP 1 MATL, REFL SHEETING, TP 9	SF	5		
636-1036	HIGHWAY SIGNS, TP 1 MATL, REFL SHEETING, TP 11	SF	25		
636-2030	GALV STEEL POSTS, TP 3	LF	10		
636-2070	GALV STEEL POSTS, TP 7	LF	60		
652-2801	SOLID TRAFFIC STRIPE, 8 IN, WHITE	LF	650		
653-1804	THERMOPLASTIC SOLID TRAF STRIPE, 8 IN, WHITE	LF	2,475		
	CONTINGENCY (at City's discretion)	LS	LUMP	-----	\$10,000.00
				GRAND TOTAL	

NOTES:

- (1) 6 – 2 ft. sections of granite curb shall be cut at 45-degree angle at each driveway apron on Church Street. The cost for this is included in the Unit Price of Reset Granite Curb.
- (2) Refer to Attachment C - Gradations Porous Concrete Sidewalk. Mix design provided to the city for approval
- (3) Refer to Attachment A - Tree Prescription Report, for tree protective measures and recommendations
- (4) Refer to Attachment B - Bench and waste receptacle (Exhibit R) specifications.
- (5) Two – 3-inch caliper trees to be installed at each bench pad. Total of 8 trees. Tree species are: Southern Sugar Maple (Acer floridanum/ Acer saccharum ssp. Floridanum) -2, Maple - Trident Acer buergerianum – 2; Crape myrtle Lagerstroemia indica; purple (single stem) – 4. Locations at the direction of the project engineer
- (6) Driveway concrete – 4000 psi mix with fiber mesh
- (7) Concrete slab for benches/waste receptacle; 10 ft. x 10 ft. each pad

SIGNATURE: _____ DATE: _____